

MODEL : RS-25-3.3

OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1: 80 mVp-p (Max)	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	V1: 28 mVp-p (Max)	P
2	OUTPUT VOLTAGE ADJUST RANGE	CH1: 2.85 V- 3.6 V	I/P: 230 VAC I/P: 115 VAC O/P:MIN LOAD Ta:25°C	2.73V- 4 V/ 230VAC 2.73V- 4 V/ 115 VAC	P
3	OUTPUT VOLTAGE TOLERANCE	V1: 3 %- -3 % (Max)	I/P: 115 VAC / 264 VAC O/P:FULL/ MIN LOAD Ta:25°C	V1: 0.6 %- -0.6 %	P
4	LINE REGULATION	V1: 0.5 %- -0.5 % (Max)	I/P: 115VAC ~ 264VAC O/P:FULL LOAD Ta:25°C	V1: 0 % - 0 %	P
5	LOAD REGULATION	V1: 2 %- -2 % (Max)	I/P: 230VAC O/P:FULL -MIN LOAD Ta:25°C	V1: 0.6 %- -0.6 %	P
6	SET UP TIME	230VAC/ 1800 ms (Max) 115VAC/ 4000 ms (Max)	I/P: 230VAC I/P: 230VAC O/P:FULL LOAD Ta:25°C	230VAC/ 1320 ms 115VAC/ 2590 ms	P
7	RISE TIME	230VAC/ 23ms (Max) 115VAC/ 30ms (Max)	I/P: 230VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230VAC/ 12 ms 115VAC/ 13 ms	P
8	HOLD UP TIME	230VAC/ 80 ms (TYP) 115VAC/ 14 ms (TYP)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230VAC/ 96 ms 115VAC/ 19 ms	P
9	OVER/UNDERSHOOT TEST	< ±5%	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	TEST: < 5 %	P
10	DYNAMIC LOAD	V1: 660 mVp-p	I/P: 230 VAC O/P:FULL /Min LOAD 90%DUTY/1KHZ Ta:25°C	338 mVp-p	P

INPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	88VAC~264VAC	I/P:TESTING O/P:FULL LOAD Ta:25°C	54 V~ 264 V	P
			I/P: LOW-LINE-3V= 85 V HIGH-LINE+15%=300 V O/P:FULL/MIN LOAD ON: 30 Sec . OFF: 30 Sec 10MIN (AC POWER ON/OFF NO DAMAGE)	TEST: OK	
2	INPUT FREQUENCY RANGE	47 HZ ~ 63 HZ NO DAMAGE OSC	I/P: 88VAC ~ 264VAC O/P:FULL-MIN LOAD Ta:25°C	TEST: OK	P
3	EFFICIENCY	73.5 % (TYP)	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	76.185 %	P
4	INPUT CURRENT	230V/ 0.4 A (TYP) 115V/ 0.7 A (TYP)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	I = 0.3 A/ 230 VAC I = 0.45 A/ 115 VAC	P
5	INRUSH CURRENT	230V/ 30 A (TYP) COLD START	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	I = 29 A/ 230 VAC	P
6	LEAKAGE CURRENT	< 2 mA / 240 VAC	I/P: 254 VAC O/P:Min LOAD Ta:25°C	L-FG: 0.6 mA N-FG: 0.6 mA	P

CONTROL FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	NO LOAD POWER CONSUMPTION	<0.5W	I/P : 230 VAC O/P : NO LOAD	0.362 W/230VAC	P

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	110 %~ 180 %	I/P: 230 VAC I/P: 115 VAC O/P:TESTING Ta:25°C	146 %/ 230 VAC 138 %/ 115 VAC Hiccup Mode	P
2	OVER VOLTAGE PROTECTION	CH1:3.8 V~ 4.45 V	I/P: 230 VAC I/P: 115 VAC O/P:MIN LOAD Ta:25°C	4.2 V/ 230 VAC 4.2 V/ 115 VAC Hiccup Model	P
3	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P: 264 VAC O/P: FULL LOAD Ta:25°C	NO DAMAGE Hiccup Mode	P

SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P: 3 KVAC/min I/P-FG: 1.5 KVAC/min O/P-FG: 0.5 KVAC/min	I/P-O/P: 3.6 KVAC/min I/P-FG: 1.8 KVAC/min O/P-FG: 0.6 KVAC/min Ta:25°C	I/P-O/P: 2.6 mA I/P-FG: 2.3 mA O/P-FG: 1.6 mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P:500VDC>100MΩ I/P-FG: 500VDC>100MΩ O/P-FG:500VDC>100MΩ	I/P-O/P: 500 VDC I/P-FG: 500 VDC O/P-FG: 500 VDC Ta:25°C	I/P-O/P: 5 G Ω I/P-FG: 3 G Ω O/P-FG: 8.7 G Ω NO DAMAGE	P
3	GROUNDING CONTINUITY	FG(PE) TO CHASSIS OR TRACE < 100 mΩ	40 A / 2min Ta:25°C	4 mΩ	P
4	APPROVAL	TUV: Certificate NO : R50046664 UL: File NO : E183223			P

E.M.C TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	HARMONIC	EN61000-3-2 CLASS A	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	PASS	P
2	CONDUCTION	EN55022 CLASS B	I/P: 230 VAC (50HZ) O/P:FULL/50% LOAD Ta:25°C	PASS Test by certified Lab	P
3	RADIATION	EN55022 CLASS B	I/P: 230 VAC (50HZ) O/P:FULL LOAD Ta:25°C	PASS Test by certified Lab	P
4	E.S.D	EN61000-4-2 LIGHT INDUSTRY AIR:8KV / Contact:4KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
5	E.F.T	EN61000-4-4 LIGHT INDUSTRY INPUT: 1KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
6	SURGE	IEC61000-4-5 LIGHT INDUSTRY L-N :1KV L,N-PE:2KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
7	Test by certified Lab & Test Report Prepare				



M.T.B.F & LIFE CYCLE CALCULATION

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	CAPACITOR LIFE CYCLE	SUPPOSE C 57 (RS-25-5) IS THE MOST CRITICAL COMPONENT I/P: 230 VAC O/P:FULL LOAD Ta= 25 °C LIFE TIME= 47925 HRS I/P: 230 VAC O/P:FULL LOAD Ta= 45 °C LIFE TIME= 20832 HRS			P
2	MTBF	MIL-HDBK-217F NOTICES2 PARTS COUNT TOTAL FAILURE RATE: 309.7K HRS			P
3	DMTBF/Accelerated Life Test	Demonstration Mean Time Between Failure : Above 30,000 hours @ TA 40°C			P

COMPONENT STRESS TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	Power Transistor (D to S) or (C to E) Peak Voltage	Q 1 Rated K2545 : 600 V 6 A	I/P:High-Line +3V = 267 V O/P: (1)Full Load Turn on (2) Full Load (3)Output Short Ta:25°C	(1) 442 V (2) 570 V (3) 578 V	P
2	Diode Peak Voltage	D 55 Rated MBR1545CT : 45 V 15 A	I/P:High-Line +3V = 267 V O/P: (1)Full Load Turn on (2) Full Load (3)Output Short Ta:25°C	(1) 15.1 V (2) 18.3 V (3) 18.3 V	P
3	Clamp Diode Peak Voltage	D 1 Rated EGP20J : 600 V 2 A	I/P:High-Line +3V = 267 V O/P: (1)Full Load (2) Dynamic Load 90%Duty/1KHz Ta:25°C	(1) 366 V (2) 384 V	P
4	Input Capacitor Voltage	C 5 Rated : 56 u 400 V 105°C	I/P:High-Line +3V = 267 V O/P: (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta:25°C	(1) 388 V (2) 372 V (3) 372 V	P
5	Control IC Voltage Test	U Rated SG684 : 30V	I/P:High-Line +3V = 267 V O/P: (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta:25°C	(1) 21.5 V (2) 17 V (3) 21.2 V	P

DATE	SAMPLE	TEST RESULT	TESTER	APPROVAL
2004/5/21	RD SAMPLE	PASS	VINCENT TSENG	MAX LIN
2004/8/2	PRODUCT SAMPLE A406A38	PASS	VINCENT TSENG	MAX LIN
2004/9/15	PRODUCT SAMPLE W0408C08	PASS	VINCENT TSENG	MAX LIN

2003/12/12 A50-F023