



Test Report: EDR-120-24

120W Single Output Industrial DIN RAIL

■ DESIGN VERIFY TEST

Output Function Test

Input Function Test

Protection Function Test

Component Stress Test

■ SAFETY & E.M.C. TEST

Safety Test

E.M.C. Test

■ RELIABILITY TEST

ENVIRONMENT TEST

■ DESIGN VERIFY TEST

MODEL : EDR-120-24

DVT TEST

OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1: 120 mVp-p (Max)	I/P: 230VAC O/P: FULL LOAD Ta: 25°C	V1: 33.8 mVp-p (Max)	P
2	OUTPUT VOLTAGE ADJUST RANGE	CH1: 24 V~28 V	I/P: 230VAC/115VAC O/P: MIN LOAD Ta: 25°C	23.23V~28.71 V/230VAC 23.23V~28.71 V/115VAC	P
3	OUTPUT VOLTAGE TOLERANCE	V1: 1%~-1% (Max)	I/P: 100VAC/264VAC O/P: FULL/ MIN. LOAD Ta: 25°C	V1: 0.074%~-0.074%	P
4	LINE REGULATION	V1: 0.5%~-0.5% (Max)	I/P: 100VAC~264VAC O/P: FULL LOAD Ta: 25°C	V1: 0.025%~-0%	P
5	LOAD REGULATION	V1: 1%~-1% (Max)	I/P: 230VAC O/P: FULL ~MIN LOAD Ta: 25°C	V1: 0.074%~-0.074%	P
6	SET UP TIME	230VAC/1200ms (Max) 115VAC/2500ms (Max)	I/P: 230VAC/115VAC O/P: FULL LOAD Ta: 25°C	230VAC/731.218ms 115VAC/1584.837ms	P
7	RISE TIME	230VAC/60ms (Max) 115VAC/60ms (Max)	I/P: 230VAC/115VAC O/P: FULL LOAD Ta: 25°C	230VAC/ 26.506ms 115VAC/27.797ms	P
8	HOLD UP TIME	230VAC/16ms (TYP) 115VAC/10ms (TYP)	I/P: 230VAC/115VAC O/P: FULL LOAD Ta: 25°C	230VAC/59.079ms 115VAC/ 12.462ms	P
9	OVER/UNDERSHOOT TEST	< ±5%	I/P: 230VAC O/P: FULL LOAD Ta: 25°C	<5%	P
10	DYNAMIC LOAD	V1: 2400 mVp-p	I/P: 230VAC O/P: (1) FULL /Min LOAD 90% DUTY/1KHZ (2) (1) FULL /Min LOAD 90% DUTY/3KHZ (3) FULL /Min LOAD 90% DUTY/5KHZ (4) FULL /Min LOAD 50% DUTY/120HZ Ta: 25°C	281mVp-p 303 mVp-p 291mVp-p 311mVp-p	P

INPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	90VAC~264VAC	I/P:TESTING O/P:FULL LOAD Ta:25°C	65.706V~264V	P
			I/P: (1)LOW-LINE-3V=87 V HIGH-LINE+15%=300 V O/P:FULL/MIN LOAD ON: 30 Sec OFF: 30 Sec 10MIN (2)230Vac ON: 0.5 Sec OFF: 0.5 Sec 20MIN (3)230Vac ON:3Sec OFF:3Sec 12HOURS (POWER ON/OFF NO DAMAGE)	TEST:OK	
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE	I/P:100 VAC ~264 VAC O/P:FULL-MIN LOAD Ta:25°C	TEST: OK	P
4	EFFICIENCY	87.5% (TYP)	I/P:230 VAC O/P:FULL LOAD Ta:25°C	89.07%	P
5	INPUT CURRENT	230V/ 1.3A (Typ) 115V/ 2.25 A (Typ)	I/P: 230 VAC/115VAC O/P:FULL LOAD Ta:25°C	I =0.99A/ 230VAC I =2.07A/ 115VAC	P
6	INRUSH CURRENT	230V/35A (Typ) 115V/20A (Typ) COLD START	I/P:230VAC/115VAC O/P:FULL LOAD Ta:25°C	I =32.437A/ 230VAC I =17.750A/ 115VAC	P

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	105%~130% RATED OUTPUT POWER	I/P: 264VAC I/P: 230VAC I/P: 100VAC O/P:TESTING Ta:25°C	113.8%/ 264VAC 113.5%/ 230VAC 114.0%/100VAC Constant Current Limiting	P
2	OVER VOLTAGE PROTECTION	CH:29V~33V(Typ)	I I/P:264VAC I/P: 230VAC I/P: 90VAC O/P:MIN LOAD Ta:25°C	30.75V/ 264VAC 30.71V/ 230VAC 30.68V/90VAC Shunt down Re- power ON	P
3	OVER TEMPERATURE PROTECTION	NO DAMAGE	I/P: 230 VAC O/P:FULL LOAD	O.T.P. Active Shut down Re-power ON	P
4	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P: 264VAC O/P: FULL LOAD Ta:25°C	NO DAMAGE Constant Current Limiting	P

COMPONENT STRESS TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	Power Transistor (D to S) or (C to E) Peak Voltage	Q1 Rated 11 A/600 V	I/P:High-Line +3V =267V O/P: (1)Full Load input on/off (2)Output Short (3) Full Load Continue Ta:25°C	(1) 518V (2) 392V (3) 514V	P
2	Diode Peak Voltage	D100 Rated 20A/ 150V	I/P:High-Line +3V =267 V O/P: (1)Full Load input on/off (2)Output Short (3) Full Load Continue Ta:25°C	(1)126V (2)107V (3)120V	P
3	Input Capacitor Voltage	C5 Rated: 180 μ / 400V	I/P:High-Line +3V =267 V O/P: (1)Full Load input on/off (2) Min load input on /Off Ta:25°C	(1)362V (2)362V	P
4	Control IC Voltage Test	PWM IC U1 1380 Rated 28 V(MAX.) 9 V(MIN.)	I/P:High-Line +3V =267 V O/P:(1)FULL LOAD (2) Output Short (3)NO LOAD VR 下限.LOW LINE Ta:25°C	(2) 17.5V (3) 17.1V (4) 16.7V	P

SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	EN 60950 I/P-O/P: 3KVAC/min I/P-FG: 2 KVAC/min O/P-FG:0.5KVAC/min	I/P-O/P: 3.6 KVAC/min I/P-FG: 2.4 KVAC/min O/P-FG:0.6 KVAC/min Ta:25°C	I/P-O/P: 3.212mA I/P-FG: 3.72mA O/P-FG: 3.96mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P:500VDC>100M Ω I/P-FG: 500VDC>100M Ω O/P-FG:500VDC>100M Ω	I/P-O/P: 500 VDC I/P-FG: 500 VDC O/P-FG: 500 VDC Ta:25°C	I/P-O/P: 9999M Ω I/P-FG: 9999M Ω O/P-FG: 9999M Ω NO DAMAGE	P
3	GROUNDING CONTINUITY	EN 60950 FG(PE) TO CHASSIS OR TRACE < 100 m Ω	40A / 2min Ta:25°C	15m Ω BY CASE	P
4	LEAKAGE CURRENT	EN 60950 1mA< 240VAC	I/P:264 VAC O/P:Min LOAD Ta:25°C	L-FG: 0.30mA N-FG:0.31mA	P

E.M.C TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	HARMONIC	EN61000-3-2 CLASS A	I/P:230VAC/50HZ O/P:100%LOAD Ta:25°C	PASS	P
2	E.S.D	EN61000-4-2 INDUSTRY AIR:8KV / Contact:4KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P

3	E.F.T	EN61000-4-4 INDUSTRY INPUT: 2KV	I/P: 230VAC/50HZ O/P: FULL LOAD Ta: 25°C	CRITERIA A	P
4	SURGE	IEC61000-4-5 INDUSTRY L-N :2KV L,N-PE:4KV	I/P: 230VAC/50HZ O/P: FULL LOAD Ta: 25°C	CRITERIA A	P

RELIABILITY TEST

ENVIRONMENT TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT																																																								
1	TEMPERATURE RISE TEST	MODEL : EDR-120-12 1. ROOM AMBIENT BURN-IN : 1HRS I/P : 230VAC O/P : FULL LOAD Ta=23.0°C 2. HIGH AMBIENT BURN-IN : 1 HRS I/P : 230VAC O/P : FULL LOAD Ta=43.5°C	<table border="1"> <thead> <tr> <th>NO</th> <th>Position</th> <th>ROOM AMBIENT Ta=23.0°C</th> <th>HIGH AMBIENT Ta=43.5°C</th> </tr> </thead> <tbody> <tr><td>1</td><td>U1</td><td>55.6°C</td><td>75.2°C</td></tr> <tr><td>2</td><td>U107</td><td>50.0°C</td><td>70.9°C</td></tr> <tr><td>3</td><td>C5</td><td>53.0°C</td><td>73.0°C</td></tr> <tr><td>4</td><td>Q1</td><td>71.2°C</td><td>91.3°C</td></tr> <tr><td>5</td><td>T1</td><td>83.7°C</td><td>103.5°C</td></tr> <tr><td>6</td><td>C105</td><td>65.7°C</td><td>86.8°C</td></tr> <tr><td>7</td><td>D5</td><td>95.3°C</td><td>115.9°C</td></tr> <tr><td>8</td><td>C36</td><td>76.3°C</td><td>95.4°C</td></tr> <tr><td>9</td><td>BD1</td><td>58.7°C</td><td>78.8°C</td></tr> <tr><td>10</td><td>D100</td><td>68.3°C</td><td>88.1°C</td></tr> <tr><td>11</td><td>D101</td><td>73.3°C</td><td>93.9°C</td></tr> <tr><td>12</td><td>RTH2</td><td>74.3°C</td><td>94.9°C</td></tr> <tr><td>13</td><td>LF2</td><td>78.5°C</td><td>98.4°C</td></tr> </tbody> </table>	NO	Position	ROOM AMBIENT Ta=23.0°C	HIGH AMBIENT Ta=43.5°C	1	U1	55.6°C	75.2°C	2	U107	50.0°C	70.9°C	3	C5	53.0°C	73.0°C	4	Q1	71.2°C	91.3°C	5	T1	83.7°C	103.5°C	6	C105	65.7°C	86.8°C	7	D5	95.3°C	115.9°C	8	C36	76.3°C	95.4°C	9	BD1	58.7°C	78.8°C	10	D100	68.3°C	88.1°C	11	D101	73.3°C	93.9°C	12	RTH2	74.3°C	94.9°C	13	LF2	78.5°C	98.4°C		P
NO	Position	ROOM AMBIENT Ta=23.0°C	HIGH AMBIENT Ta=43.5°C																																																										
1	U1	55.6°C	75.2°C																																																										
2	U107	50.0°C	70.9°C																																																										
3	C5	53.0°C	73.0°C																																																										
4	Q1	71.2°C	91.3°C																																																										
5	T1	83.7°C	103.5°C																																																										
6	C105	65.7°C	86.8°C																																																										
7	D5	95.3°C	115.9°C																																																										
8	C36	76.3°C	95.4°C																																																										
9	BD1	58.7°C	78.8°C																																																										
10	D100	68.3°C	88.1°C																																																										
11	D101	73.3°C	93.9°C																																																										
12	RTH2	74.3°C	94.9°C																																																										
13	LF2	78.5°C	98.4°C																																																										
2	OVER LOAD BURN-IN TEST	NO DAMAGE 1 HOUR (MIN)	I/P : 230 VAC O/P : 108% LOAD Ta : 25°C	TEST : OK	P																																																								
3	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR	I/P : 264VAC/100VAC O/P : 100 % LOAD Ta= -20°C	TEST : OK	P																																																								
4	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL 45°C NO DAMAGE	I/P : 272 VAC O/P : FULL LOAD Ta=45°C HUMIDITY= 95 %R.H	TEST : OK	P																																																								
5	TEMPERATURE COEFFICIENT	±0.03%/°C (0~50°C)	I/P : 230 VAC O/P : FULL LOAD	0%/°C (0~50°C)	P																																																								

6	STORAGE TEMPERATURE TEST	1. Thermal shock Temperature : -40°C~ +85°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 5 CYCLE 5. Input/Output condition : STATIC	OK	P
7	THERMAL SHOCK TEST	1. Thermal shock Temperature : -20°C~ +70°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 10 CYCLE 5. Input/Output condition : 230VAC/Full Load AC ON/OFF TEST turn on 58sec ; turn off 2sec	OK	P
8	VIBRATION TEST	1 Carton & 1 Set (1) Waveform : Sine Wave (2) Frequency : 10~500Hz (3) Sweep Time : 12min/sweep cycle (4) Acceleration : 2G (5) Test Time : 60min in each axis (X.Y.Z) (6) Ta : 25°C	TEST : OK	P
9	CAPACITOR LIFE CYCLE	SUPPOSE C105 IS THE MOST CRITICAL COMPONENT (1) I/P : 230VAC O/P : FULL LOAD Ta=25°C LIFE TIME (2) I/P : 230VAC O/P : FULL LOAD Ta=45°C LIFE TIME (3) I/P : 230VAC O/P : 75% LOAD Ta=45°C LIFE TIME (4) I/P : 230VAC O/P : 50% LOAD Ta=45°C LIFE TIME	(1) 132585HRS (2) 32658HRS (3) 48474HRS (4) 93765HRS	P
10	MTBF	MIL-HDBK-217F TOTAL FAILURE RATE : 474.6KHRS		P
11	DMTBF/Accelerated Life Test	Demonstration Mean Time Between Failure (Expected Life): Above 50,000 hours @ TA 50°C		P

SAMPLE	TESTER	APPROVAL
PRODUCT SAMPLE	FRANK	WANGDZ

2007/3/20 A50-S014