



Test Report:RSP-500-05

500W Single Output Switching Power Supply

■ DESIGN VERIFY TEST

Output Function Test

Input Function Test

Protection Function Test

Control Function Test

Component Stress Test

■ SAFETY & E.M.C. TEST

Safety Test

E.M.C. Test

■ RELIABILITY TEST

ENVIRONMENT TEST

■ DESIGN VERIFY TEST

OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1 : 150 mVp-p (Max)	I/P : 230VAC O/P : FULL LOAD Ta : 25°C	V1 : 75 mVp-p (Max)	P
2	OUTPUT VOLTAGE ADJUST RANGE	CH1 : 4.5 V ~ 5.5 V	I/P : 230 VAC I/P : 115 VAC O/P : MIN LOAD Ta : 25°C	4.355 V~ 5.705 V/ 230 VAC 4.352 V~ 5.702 V/ 115 VAC	P
3	OUTPUT VOLTAGE TOLERANCE	V1 : -2 %~ +2 % (Max)	I/P : 100 VAC / 264 VAC O/P : FULL/ MIN LOAD Ta : 25°C	V1 : 0 %~ 0.25 %	P
4	LINE REGULATION	V1 : -0.5 %~ +0.5 % (Max)	I/P : 100 VAC ~ 264 VAC O/P : FULL LOAD Ta : 25°C	V1 : 0 %~ 0 %	P
5	LOAD REGULATION	V1 : -1 %~ +1 % (Max)	I/P : 230 VAC O/P : FULL ~MIN LOAD Ta : 25°C	V1 : 0 %~ 0.12 %	P
6	SET UP TIME	230VAC : 1500 ms (Max) 115VAC : 3000 ms (Max)	I/P : 230 VAC/115VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 726 ms 115VAC/ 2083 ms	P
7	RISE TIME	230VAC : 80 ms (Max) 115VAC : 80 ms (Max)	I/P : 230 VAC/115VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 10.1 ms 115VAC/ 10.3 ms	P
8	HOLD UP TIME	230VAC : 18 ms (Max) 115VAC : 14 ms (Max)	I/P : 230 VAC/115VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 23.8 ms 115VAC/ 17.8 ms	P
9	OVER/UNDERSHOOT TEST	< ±10%	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	TEST : <10 %	P
10	DYNAMIC LOAD	V1 : 1500 mVp-p	I/P : 230 VAC (1).O/P : FULL /Min LOAD 90%DUTY/ 1KHZ (2).O/P : FULL /Min LOAD 90%DUTY/ 3KHZ (3).O/P : FULL /Min LOAD 90%DUTY/ 5KHZ (4).O/P : FULL /Min LOAD 50%DUTY/ 120HZ Ta : 25°C	(1) 444 mVp-p (2) 400 mVp-p (3) 403 mVp-p (4) 936 mVp-p	P

INPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	85VAC~264 VAC	I/P : TESTING O/P : FULL LOAD Ta : 25°C I/P : LOW-LINE-3V= 82 V HIGH-LINE+15%=300 V O/P : FULL/MIN LOAD ON : 30 Sec. OFF : 30 Sec 10MIN (AC POWER ON/OFF NO DAMAGE) NOR-LINE FULL LOAD ON: 2 SEC OFF: 2 SEC 12 HOURS	63 V~264V TEST : OK	P
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE OSC	I/P : 85 VAC ~ 264 VAC O/P : FULL~MIN LOAD Ta : 25°C	TEST : OK	P
3	POWER FACTOR	0.95 / 230 VAC(TYP) 0.98 / 115 VAC(TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	PF= 0.968 / 230 VAC PF= 0.990 / 115 VAC	P
4	EFFICIENCY	83.5 % (TYP)	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	83.75 %	P
5	INPUT CURRENT	230V/ 2.65 A (TYP) 115V/ 5.3 A (TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	I = 2.478 A/ 230 VAC I = 4.963 A/ 115 VAC	P
6	INRUSH CURRENT	230V/ 40 A (TYP) 115V/ 20 A (TYP) COLD START	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	I = 35.8 A/ 230VAC I = 17.3 A/115VAC	P
7	LEAKAGE CURRENT	< 2 mA / 240VAC	I/P : 264 VAC O/P : Min LOAD Ta : 25°C	L-FG : 0.68 mA N-FG : 0.68 mA	P

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	105 % ~130 %	I/P : 230 VAC I/P : 115 VAC O/P : TESTING Ta : 25°C	108.9 %/230VAC 109.4 %/115VAC Constant Current Limiting	P
2	OVER VOLTAGE PROTECTION	CH1 : 5.75 V ~ 6.75 V	I/P : 230 VAC I/P : 115 VAC O/P : MIN LOAD Ta : 25°C	6.042 V/230VAC 6.072 V/ 115 VAC Shut down Re- power ON	P
3	OVER TEMPERATURE PROTECTION	SPEC : Shut down o/p voltage , recovers automatically after temperature goes down	I/P : 230 VAC O/P : FULL LOAD	O.T.P. Active Shut down o/p voltage , recovers automatically after temperature goes down	P
4	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P : 264 VAC O/P : FULL LOAD Ta : 25°C	NO DAMAGE Constant Current Limiting	P

CONTROL FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	REMOTE CONTROL	CN100 POWER ON : < 0~0.8V" POWEROFF : 4~10V"	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	POWER ON : 0~1.1 V POWER OFF : 1.2~10 V	P
2	REMOTE SENSE	S+ / S- >0.3V	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	0.35	P

COMPONENT STRESS TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	Power Transistor (D to S) or (C to E) Peak Voltage	Q 4 Rated : 650V 16A	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2) Output Short (3)Full load continue (4) Dynamic Load 90%Duty/1KHz (5) Dynamic Load 50%Duty/120Hz Ta : 25°C	(1) 404 V (2) 416 V (3) 396 V (4) 400 V (5) 396 V	P
2	Diode Peak Voltage	Q103 Rated : 40V 120 A	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2)Output Short (3)Full load continue (4)NO LOAD TURN ON (5) Dynamic Load 90%Duty/1KHz (6) Dynamic Load 50%Duty/120Hz Ta : 25°C	(1) 38 V (2) 37 V (3) 36 V (4) 27.5 V (5) 39.5 V (6) 38.6 V	P
3	Input Capacitor Voltage	C 5 Rated : 180u /400V/105°C	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 380 V (2) 376 V (3) 392 V	P
4	Control IC Voltage Test	U 1 Rated : 30 V	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 16.3 V (2) 15.9 V (3) 16.2 V	P
5	PFC Transistor (D to S) or (C to E) Peak Voltage	Q 1 Rated : 600 V 20 A	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2) Output Short (3) Full load continue (4)Dynamic Load 50%Duty/120Hz Ta : 25°C	(1) 406 V (2) 389 V (3) 408 V (4) 403 V	P

■ SAFETY & E.M.C. TEST

SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P : 3KVAC/min I/P-FG : 2KVAC/min O/P-FG : 0.5 KVAC/min	I/P-O/P: 3.6 KVAC/min I/P-FG : 2.4 KVAC/min O/P-FG : 0.6 KVAC/min Ta : 25°C	I/P-O/P : 3.06 mA I/P-FG : 3.15 mA O/P-FG : 3.09 mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P : 500VDC>100MΩ I/P-FG : 500VDC>100MΩ O/P-FG : 500VDC>100MΩ	I/P-O/P : 500 VDC I/P-FG : 500 VDC O/P-FG : 500 VDC Ta : 25°C/70%RH	I/P-O/P : 9999 MΩ I/P-FG : 9999 MΩ O/P-FG : 9999 MΩ NO DAMAGE	P
3	GROUNDING CONTINUITY	FG(PE) TO CHASSIS OR TRACE < 100 mΩ	40 A / 2min Ta : 25°C / 70%RH	5 mΩ	P

E.M.C TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	HARMONIC	EN61000-3-2 CLASS A CLASS D	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	PASS	P
2	CONDUCTION	EN55022 CLASS B	I/P : 230 VAC (50HZ) O/P : FULL/50% LOAD Ta : 25°C	PASS Test by certified Lab	P
3	RADIATION	EN55022 CLASS B	I/P : 230 VAC (50HZ) O/P : FULL LOAD Ta : 25°C	PASS Test by certified Lab	P
4	E.S.D	EN61000-4-2 INDUSTRY AIR : 8KV / Contact : 4KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
5	E.F.T	EN61000-4-4 INDUSTRY INPUT : 2KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
6	SURGE	IEC61000-4-5 INDUSTRY L-N : 2KV L,N-PE : 4KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
7	Test by certified Lab & Test Report Prepare				

■ RELIABILITY TEST

ENVIRONMENT TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT																																																																																																																												
1	TEMPERATURE RISE TEST	MODEL : RSP-500-05			P																																																																																																																												
		1. ROOM AMBIENT BURN-IN : 2 HRS I/P : 230VAC O/P : FULL LOAD Ta=19.6°C																																																																																																																															
		2. HIGH AMBIENT BURN-IN : 2 HRS I/P : 230VAC O/P : FULL LOAD Ta=49.2°C																																																																																																																															
				<table border="1"> <thead> <tr> <th>NO</th> <th>Position</th> <th>ROOM AMBIENT Ta= 19.6°C</th> <th>HIGH AMBIENT Ta= 49.2°C</th> </tr> </thead> <tbody> <tr><td>1</td><td>TSW2</td><td>34.8°C</td><td>62.4°C</td></tr> <tr><td>2</td><td>C105</td><td>45.9°C</td><td>76.6°C</td></tr> <tr><td>3</td><td>RG1</td><td>60.7°C</td><td>90.6°C</td></tr> <tr><td>4</td><td>Q101</td><td>41.3°C</td><td>69.5°C</td></tr> <tr><td>5</td><td>Q105</td><td>51.7°C</td><td>82.4°C</td></tr> <tr><td>6</td><td>Q104</td><td>52.6°C</td><td>84.6°C</td></tr> <tr><td>7</td><td>Q103</td><td>53.4°C</td><td>84.1°C</td></tr> <tr><td>8</td><td>L100</td><td>80.2°C</td><td>113.0°C</td></tr> <tr><td>9</td><td>T1core</td><td>72.2°C</td><td>105.6°C</td></tr> <tr><td>10</td><td>T1coil</td><td>79.2°C</td><td>112.0°C</td></tr> <tr><td>11</td><td>Q4</td><td>78.2°C</td><td>114.3°C</td></tr> <tr><td>12</td><td>Q3</td><td>66.9°C</td><td>101.2°C</td></tr> <tr><td>13</td><td>U1</td><td>50.3°C</td><td>78.7°C</td></tr> <tr><td>14</td><td>T2</td><td>61.5°C</td><td>92.4°C</td></tr> <tr><td>15</td><td>C61</td><td>42.4°C</td><td>70.8°C</td></tr> <tr><td>16</td><td>TSW1</td><td>40.6°C</td><td>68.4°C</td></tr> <tr><td>17</td><td>C6</td><td>35.3°C</td><td>61.8°C</td></tr> <tr><td>18</td><td>C5</td><td>34.3°C</td><td>60.7°C</td></tr> <tr><td>19</td><td>L100</td><td>38.5°C</td><td>67.3°C</td></tr> <tr><td>20</td><td>D10</td><td>51.9°C</td><td>78.2°C</td></tr> <tr><td>21</td><td>Q2</td><td>47.2°C</td><td>75.3°C</td></tr> <tr><td>22</td><td>Q1</td><td>48.2°C</td><td>76.5°C</td></tr> <tr><td>23</td><td>BD1</td><td>43.6°C</td><td>70.9°C</td></tr> <tr><td>24</td><td>ZNR2</td><td>33.1°C</td><td>60.2°C</td></tr> <tr><td>25</td><td>LF2</td><td>32.1°C</td><td>59.2°C</td></tr> <tr><td>26</td><td>LF1</td><td>27.1°C</td><td>53.5°C</td></tr> <tr><td>27</td><td>ZNR1</td><td>24.8°C</td><td>50.6°C</td></tr> <tr><td>28</td><td>U100</td><td>36.8°C</td><td>64.3°C</td></tr> <tr><td>29</td><td>U202</td><td>50.1°C</td><td>79.1°C</td></tr> <tr><td>30</td><td>D5</td><td>42.1°C</td><td>70.5°C</td></tr> </tbody> </table>		NO	Position	ROOM AMBIENT Ta= 19.6°C	HIGH AMBIENT Ta= 49.2°C	1	TSW2	34.8°C	62.4°C	2	C105	45.9°C	76.6°C	3	RG1	60.7°C	90.6°C	4	Q101	41.3°C	69.5°C	5	Q105	51.7°C	82.4°C	6	Q104	52.6°C	84.6°C	7	Q103	53.4°C	84.1°C	8	L100	80.2°C	113.0°C	9	T1core	72.2°C	105.6°C	10	T1coil	79.2°C	112.0°C	11	Q4	78.2°C	114.3°C	12	Q3	66.9°C	101.2°C	13	U1	50.3°C	78.7°C	14	T2	61.5°C	92.4°C	15	C61	42.4°C	70.8°C	16	TSW1	40.6°C	68.4°C	17	C6	35.3°C	61.8°C	18	C5	34.3°C	60.7°C	19	L100	38.5°C	67.3°C	20	D10	51.9°C	78.2°C	21	Q2	47.2°C	75.3°C	22	Q1	48.2°C	76.5°C	23	BD1	43.6°C	70.9°C	24	ZNR2	33.1°C	60.2°C	25	LF2	32.1°C	59.2°C	26	LF1	27.1°C	53.5°C	27	ZNR1	24.8°C	50.6°C	28	U100	36.8°C	64.3°C	29	U202	50.1°C	79.1°C	30	D5	42.1°C	70.5°C
		NO	Position	ROOM AMBIENT Ta= 19.6°C		HIGH AMBIENT Ta= 49.2°C																																																																																																																											
		1	TSW2	34.8°C		62.4°C																																																																																																																											
		2	C105	45.9°C		76.6°C																																																																																																																											
		3	RG1	60.7°C		90.6°C																																																																																																																											
		4	Q101	41.3°C		69.5°C																																																																																																																											
		5	Q105	51.7°C		82.4°C																																																																																																																											
		6	Q104	52.6°C		84.6°C																																																																																																																											
		7	Q103	53.4°C		84.1°C																																																																																																																											
		8	L100	80.2°C		113.0°C																																																																																																																											
		9	T1core	72.2°C		105.6°C																																																																																																																											
		10	T1coil	79.2°C		112.0°C																																																																																																																											
		11	Q4	78.2°C		114.3°C																																																																																																																											
		12	Q3	66.9°C		101.2°C																																																																																																																											
		13	U1	50.3°C		78.7°C																																																																																																																											
		14	T2	61.5°C		92.4°C																																																																																																																											
		15	C61	42.4°C		70.8°C																																																																																																																											
		16	TSW1	40.6°C		68.4°C																																																																																																																											
		17	C6	35.3°C		61.8°C																																																																																																																											
		18	C5	34.3°C		60.7°C																																																																																																																											
		19	L100	38.5°C		67.3°C																																																																																																																											
		20	D10	51.9°C		78.2°C																																																																																																																											
		21	Q2	47.2°C		75.3°C																																																																																																																											
		22	Q1	48.2°C		76.5°C																																																																																																																											
		23	BD1	43.6°C		70.9°C																																																																																																																											
		24	ZNR2	33.1°C		60.2°C																																																																																																																											
		25	LF2	32.1°C		59.2°C																																																																																																																											
		26	LF1	27.1°C		53.5°C																																																																																																																											
27	ZNR1	24.8°C	50.6°C																																																																																																																														
28	U100	36.8°C	64.3°C																																																																																																																														
29	U202	50.1°C	79.1°C																																																																																																																														
30	D5	42.1°C	70.5°C																																																																																																																														
2	OVER LOAD BURN-IN TEST	NO DAMAGE 1 HOUR (MIN)	I/P : 230 VAC O/P : 118 % LOAD Ta : 25°C	TEST : OK	P																																																																																																																												
3	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR	I/P : 264VAC/100VAC O/P : 100 % LOAD Ta= -35°C	TEST : OK	P																																																																																																																												
4	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL 50 °C NO DAMAGE	I/P : 272 VAC O/P : FULL LOAD Ta=50.8°C HUMIDITY= 95 %R.H	TEST : OK	P																																																																																																																												

5	TEMPERATURE COEFFICIENT	$\pm 0.05\%/^{\circ}\text{C}$ (0~50°C)	I/P : 230 VAC O/P : FULL LOAD	$\pm 0\%/^{\circ}\text{C}$ (0~50°C)	P
6	STORAGE TEMPERATURE TEST	1. Thermal shock Temperature : -40°C ~ +85°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 5 CYCLE 5. Input/Output condition : STATIC		OK	P
7	THERMAL SHOCK TEST	1. Thermal shock Temperature : -30°C ~ +70°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 10 CYCLE 5. Input/Output condition : 230VAC/Full Load AC ON/OFF TEST turn on 58sec ; turn off 2sec		OK	P
8	VIBRATION TEST	1 Carton & 1 Set (1) Waveform : Sine Wave (2) Frequency : 10~500Hz (3) Sweep Time : 12min/sweep cycle (4) Acceleration : 2G (5) Test Time : 60min in each axis (X.Y.Z) (6) Ta : 25°C		TEST : OK	P
9	CAPACITOR LIFE CYCLE	SUPPOSE C105 IS THE MOST CRITICAL COMPONENT (1) I/P : 230VAC O/P : FULL LOAD Ta= 25°C LIFE TIME (2) I/P : 230VAC O/P : FULL LOAD Ta=50°C LIFE TIME (3) I/P : 230VAC O/P : 75% LOAD Ta= 50°C LIFE TIME (4) I/P : 230VAC O/P : 50% LOAD Ta= 50°C LIFE TIME		(1) 481016HRS (2) 78735HRS (3) 168867HRS (4) 257720HRS	P
10	MTBF	MIL-HDBK-217F NOTICE S2 PARTS COUNT TOTAL FAILURE RATE : 187.7 KHRS			P
11	DMTBF/Accelerated Life Test	Demonstration Mean Time Between Failure (Expected Life): Above 30,000 hours @ TA 50°C			P

SAMPLE	TEST RESULT	TESTER	APPROVAL
PRODUCT SAMPLE	PASS	Shenym	Wangdz

2007/3/20 A50-S014