



MODEL : LPV-100-36

OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1: 150 mVp-p (Max)	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	V1: 8 mVp-p (Max)	PASS
2	OUTPUT VOLTAGE TOLERANCE	V1: -5%~ +5% (Max)	I/P: 100VAC / 264 VAC O/P:FULL/ 0% LOAD Ta:25°C	V1: -0.2%~ 0.1 %	PASS
3	LINE REGULATION	V1: -1%~ +1% (Max)	I/P: 100 VAC ~ 264VAC O/P:FULL LOAD Ta:25°C	V1: -0.03%~ 0.05 %	PASS
4	LOAD REGULATION	V1: -2%~ +2% (Max)	I/P: 230 VAC O/P:FULL ~MIN LOAD Ta:25°C	V1: -0.06%~ 0.1 %	PASS
5	SET UP TIME	230VAC/ 2000 ms (Max) 115VAC/ 2000 ms (Max)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230 VAC/656.027ms 115 VAC/1429.834ms	PASS
6	RISE TIME	230VAC/ 25 ms (Max) 115 VAC/ 25 ms (Max)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230 VAC/13.654ms 115 VAC/11.775ms	PASS
7	HOLD UP TIME	230VAC/ 50ms (Typ) 115VAC/ 14ms (Typ)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230VAC/86.643ms 115 VAC/18.189ms	PASS
8	OVER/UNDERSHOOT TEST	< ±5 %	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	TEST: +1.66 % -1.66 %	PASS
9	DYNAMIC LOAD	V1: 3600 mVp-p	I/P: 230 VAC O/P: (1)FULL /Min LOAD 90%DUTY/1KHZ (2)FULL /Min LOAD 50%DUTY/120HZ Ta:25°C	(1) 412 mVp-p (2) 556 mVp-p	PASS

INPUT FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	90 VAC~ 264 VAC	I/P: TESTING O/P: FULL LOAD Ta: 25°C	90 V~ 264 V	PASS
			(1) I/P: LOW-LINE-3V= 87 V HIGH-LINE+15%= 300 V O/P: FULL/MIN LOAD ON: 30 Sec . OFF: 30 Sec 10MIN (2) I/P: 230VAC ON: 0.5 Sec . OFF: 0.5 Sec 20MIN (AC POWER ON/OFF NO DAMAGE)	TEST: (1) OK (2) OK	
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE OSC	I/P: 90 VAC ~264 VAC O/P: FULL~MIN LOAD Ta: 25°C	TEST: OK	PASS
3	EFFICIENCY	88 % (Typ)	I/P: 230 VAC O/P: FULL LOAD Ta: 25°C	89.006 %	PASS
4	INPUT CURRENT	230 V/ 1.2 A (Typ) 115 V/ 2.2 A (Typ)	I/P: 230 VAC I/P: 115 VAC O/P: FULL LOAD Ta: 25°C	I = 0.8212A/ 230VAC I = 1.4710A/ 115VAC	PASS
5	INRUSH CURRENT	230 V/ 75 A 115 V/ 30 A COLD START	I/P: 230 VAC I/P: 115 VAC O/P: FULL LOAD Ta: 25°C	I = 69.976A/ 230VAC I = 26.835A/ 115VAC	PASS

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	110%~ 150 % RATED OUTPUT POWER	I/P: 264 VAC I/P: 230 VAC I/P: 100 VAC O/P: TESTING Ta: 25°C	121.40 %/264VAC 127.83 %/ 230VAC 126.22 %/ 100 VAC Hiccup Mode	PASS
2	OVER VOLTAGE PROTECTION	CH1: 41.4 V~ 48.6 V	I/P: 264 VAC I/P: 230 VAC I/P: 90 VAC O/P: MIN LOAD Ta: 25°C	42.25 V/264VAC 42.44 V/ 230VAC 42.18 V/ 90 VAC Shunt down Re- power ON	PASS
3	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P: 264 VAC O/P: FULL LOAD Ta: 25°C	NO DAMAGE Hiccup Mode	PASS

ENVIRONMENT TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	TEMPERATURE RISE TEST	MODEL : LPV-100-24 1. ROOM AMBIENT BURN-IN : 2 HRS I/P: 230 VAC O/P: 100% LOAD Ta= 25.5 °C 2. HIGH AMBIENT BURN-IN : 2 HRS I/P: 230 VAC O/P: 100% LOAD Ta= 52.3 °C			PASS
2	OVER LOAD BURN-IN TEST	NO DAMAGE 1 HOUR (MIN)	I/P: 230 VAC O/P: 133 % LOAD Ta:25°C	TEST : OK	PASS
3	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR	I/P: 264 VAC/100 VAC O/P: 100% LOAD Ta= -25 °C	TEST : OK	PASS
4	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL 50 °C NO DAMAGE	I/P: 272 VAC O/P:FULL LOAD Ta= 50 °C HUMIDITY= 95 %R.H	TEST : OK	PASS
5	TEMPERATURE COEFFICIENT	± 0.03 %(0~50°C)	I/P: 230 VAC O/P:FULL LOAD	± 0.005 %(0~50°C)	PASS
6	STORAGE TEMPERATURE TEST	1. Thermal shock Temperature : -40°C~ +80°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 5 CYCLE 5. Input/Output condition : STATIC		TEST : OK	PASS
7.	THERMAL SHOCK TEST	1. Thermal shock Temperature : -30 °C~ +45 °C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 10 CYCLE 5. Input/Output condition : 230VAC/Full Load 58SEC ON/2SEC OFF		TEST : OK	PASS

8	VIBRATION TEST	1 Carton & 1 Set (1) Waveform: Sine Wave (2) Frequency:10~500Hz (3) Sweep Time:12min/sweep cycle (4) Acceleration:2G (5) Test Time:1 hour in each axis (X.Y.Z) (6) Ta:25°C	TEST : OK	PASS
9	CAPACITOR LIFE CYCLE	SUPPOSE C106 IS THE MOST CRITICAL COMPONENT (1) I/P: 230 VAC O/P:FULL LOAD Ta= 25 °C LIFE TIME= 83288.4 HRS (2) I/P: 230 VAC O/P:FULL LOAD Ta= 50 °C LIFE TIME= 27875.2 HRS (3) I/P: 230 VAC O/P:75% LOAD Ta= 50 °C LIFE TIME= 57661.2 HRS (4) I/P: 230 VAC O/P:50% LOAD Ta= 50 °C LIFE TIME= 116221.6 HRS		PASS
10	MTBF	MIL-HDBK-217F NOTICES2 PARTS COUNT TOTAL FAILURE RATE: 703K HRS		PASS
11	DMTBF/Accelerated Life Test	Demonstration Mean Time Between Failure(Expected Life) : 20,000 hours @ Tcase 85°C; 50,000 hours @ Tcase70°C		PASS

SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P: 3 KVAC/min EN 60950	I/P-O/P: 3.6 KVAC/min Ta:25°C	I/P-O/P: 2.327 mA NO DAMAGE	PASS
2	ISOLATION RESISTANCE	I/P-O/P:500VDC>100MΩ	I/P-O/P: 500 VDC Ta:25°C	I/P-O/P: >9999 MΩ NO DAMAGE	PASS
3	LEAKAGE CURRENT	< 0.25 mA / 240VAC EN 60950	I/P: 264 VAC O/P:NO LOAD Ta:25°C	L-FG: 0.005 mA N-FG: 0.003 mA	PASS

E.M.C TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	HARMONIC	EN61000-3-2 CLASS A	I/P: 220/230/240 VAC/50HZ O/P:100%/75%/50%/25% LOAD Ta:25°C	PASS	PASS
2	CONDUCTION	EN55022 CLASS B	I/P:230 VAC (50HZ) /115V(60HZ) O/P:FULL/50% LOAD Ta:25°C	PASS Test by certified Lab	PASS
3	RADIATION	EN55022 CLASS B	I/P: 230 VAC (50HZ)/115V(60HZ) O/P:FULL LOAD Ta:25°C	PASS Test by certified Lab	PASS
4	E.S.D	EN61000-4-2 INDUSTRY AIR:8KV / Contact:4KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	PASS
5	E.F.T	EN61000-4-4 INDUSTRY INPUT: 2KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	PASS
6	SURGE	IEC61000-4-5 INDUSTRY L-N :2KV L,N-PE:4KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	PASS
7	Test by certified Lab & Test Report Prepare				



COMPONENT STRESS TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	Power Transistor (D to S) or (C to E) Peak Voltage	Q 1 Rated STF14NM65N : 650 V 12 A	I/P:High-Line +3V = 280 V O/P: (1)Full Load Turn on (2)Output Short (3)Dynamic Load 50% Load/ Min. Load 90%Duty/1KHz (4)Dynamic Load Full Load/ Min. Load 90%Duty/1KHz Ta:25°C	(1) 598 V (2) 502 V (3) 606 V (4) 588 V	PASS
2	Diode Peak Voltage	D 100 Rated FCF10A40: 400V/10A	I/P:High-Line +3V = 280 V O/P: (1)Full Load Turn on (2)Output Short (3)Dynamic Load 50% Load/ Min. Load 90%Duty/1KHz (4)Dynamic Load Full Load/ Min. Load 90%Duty/1KHz Ta:25°C	(1) 214 V (2) 223 V (3) 200 V (4) 194 V	PASS
3	Clamp Diode Peak Voltage	D 1 Rated 1N5406 : 600 V 3A	I/P:High-Line +3V = 280 V O/P: (1)Dynamic Load 50% Load/ Min. Load 90%Duty/1KHz (2)Dynamic Load Full Load/ Min. Load 90%Duty/1KHz Ta:25°C	(1) 434 V (2) 432 V	PASS
4	Control IC Voltage Test	U 1 Rated NCP1380BDR2G : 28 V	I/P:High-Line +3V =280 V O/P: (1) Output Short (2)O.L.P (3)O.V.P Ta:25°C	(1) 17.3 V (2) 17.3 V (3) 16.3 V	PASS

2007/11/26 A50-G058

DATE	SAMPLE	TEST RESULT	TESTER	APPROVAL
2010/5/20	RD SAMPLE	PASS	ZOULF	HOWAY
2011/1/6	PRODUCT SAMPLE (W1012I095)	PASS	ZOULF	HOWAY
2011/3/31	PRODUCT SAMPLE (W1103G134)	PASS	ZOULF	HOWAY